Item 3 – Selection of a Drilling Contractor | Simsboro Monitoring Well

The Texas Water Development Board (TWDB) included grant funding to the District in the amount of $190,000 to construct a Simsboro monitoring well between Hearne, Texas and Calvert, Texas. A pressure transducer will also be installed once the well has been completed.

The General Manager has reached out to several drilling contractors and solicited bid proposals for the construction. Some of the entities were either incapable of drilling to depth or had no interest in dealing with the steel-casing construction. Three (3) of the entities expressed interest, but only two (2) have entered proposals to the District. Below are the results of the bid solicitation:

Contractor	Location	Bid Proposal
Brien Water Wells	Hearne, Texas	$183,700
J&S Water Wells	Bellville, Texas	$190,168
Weisinger, Inc.	Willis, Texas	NO BID RECEIVED

Attached are the bid proposals the District received for your review.

It is the recommendation by the General Manager for the Board to accept the bid proposal received from Brien Water Wells and move forward with construction of the Simsboro monitoring well.

BRIEN WATER WELLS

5214 S. HWY 6
HEARNE TX 77859
979-279-2427

Estimate

Date	Estimate #
9/26/2026	4" SIMSBORO

Name / Address
BRAZOS VALLEY GROUNDWATER DISTRICT PO BOX 528 HEARNE, TEXAS 77859

Description	Qty	Total
MOB/DEMOB, SET CONDUCTOR, DRILL TEST HOLE TO 820 FT AND E-LOG. VARIBLE COST OF TEST HOLE IS $30.00 PER FOOT.	1	78,300.00
REAM TEST HOLE, SET 700 FT OF 4" BLACK CASING, 100 FT OF 4" STAINLESS STEEL PIPE BASED SCREEN, GRAVEL PACK, PRESSURE CEMENT AND DEVELOP MONITOR WELL. INSTALL LOCKABLE WELL HEAD AND CEMENT SLAB. VARIBLE COST OF 4" BLANK CASING SET IN WELL IS $45.00 PER FOOT. VARIBLE COST OF 4" SCREEN SET IN WELL IS $75.00 PER FOOT.	1	105,400.00
BID ASSUMES WELL NEAR OIL PAD WILL BE USED FOR WATER SUPPLY. BID ASSUMES BRAZOS VALLEY GCD WILL PROVIDE DRILLING PERMIT FOR THE MONITOR WELL.		

	Total	$183,700.00

Customer Signature _____

J & S Water Wells
PO Box 675
Bellville, Texas 77418
Office 979-865-2393

Quotation

Brazos Valley Groundwater Conservation District
112 W 3rd Street
Hearne, Texas 77859
aday@brazosvalleygcd.com
979-279-9350

9/21/2026
Valid for 30 days

Job Name: 4 inch Monitor Well

Terms: Due on receipt

Qty				
1	Mobilization	Drill rig, water truck, backhoe	$ 43,000.00	$ 43,000.00
1000	Drilling	Drill pilot hole 8 3/4"	$ 23,000.00	$ 23,000.00
1000	Reaming	Ream pilot hole to 10"	$ 21,000.00	$ 21,000.00
900	Casing	4 Inch Steel casing	$ 50,000.00	$ 50,000.00
100	Screen	4 inch Screen	$ 25,000.00	$ 25,000.00
110	Gravel Pack	#1 Filtersil via tremie pipe	$ 2,633.00	$ 2,633.00
900	Grout	Cement annular seal	$ 5,000.00	$ 5,000.00
1	Cement Slab	Seal block surface slab with sleeve	$ 535.00	$ 535.00
1	Geophysical Log	Geophysical Log (Basic)	$ 20,000.00	$ 20,000.00
			Well Total:	$ 190,168.00

NOTES:
No guarantee on water quality or quantity
Operating permit provided by customer prior to scheduling
Drilling make up water provided by customer
No trenching or electrical beyond well head included
Lack of power to controls does not constitute withholding of payment
All weather access provided by customer
Drill cuttings and drilling mud disposed of on site

Quote By: Shaun Grell

Add/Deduct Values:

Drilling:	$ 23.00	per foot
Reaming:	$ 28.00	per foot
Casing:	$ 28.00	per foot
Screen	$ 190.00	per foot

Regulated by: Texas Department of Licensing & Regulation, P.O. Box 12157, Austin, Texas 78711
800-803-9202 or 512-463-7880